

Dirksen Annex Program						
Space	#	Space Category	CPS GSF	Actual GSF	Difference	Notes
TEACHING STATIONS	1	CR-01	760	760	0	
	1	CR-02	760	866	106	
	1	CR-03	760	760	0	
	1	CR-04	760	866	106	
	1	CR-05	760	760	0	
	1	CR-06	760	866	106	
	1	CR-07	760	760	0	
	1	CR-08	760	760	0	
	1	CR-09	760	760	0	
	1	CR-10	760	760	0	
	1	CR-11	760	760	0	
	1	CR-12	760	860	100	
	1	CR-13	760	760	0	
	1	CR-14	760	860	100	
	1	CR-15	760	760	0	
	1	CR-16	760	860	100	
	1	CR-17	760	760	0	
	1	CR-18	760	760	0	
	1	SN-01	760	859	99	
	1	SN-02	760	859	99	
	1	SN-03	760	866	106	
	1	SN-04	760	865	105	
	1	Pre-K / Kindergarten-01	1,180	1,140	-40	
	1	Pre-K / Kindergarten-02	1,180	1,140	-40	
	1	Pre-K / Kindergarten-03	1,180	1,140	-40	
	1	Pre-K / Kindergarten-04	1,180	1,140	-40	
	1	Science Classroom (w/ storage)	1,080	1,386	306	
	1	Science Classroom (w/ storage)	1,080	1,417	337	
	1	Computer CR-01	1,040	1,285	245	
	1	Computer CR-02	1,040	1,520	480	
ADMIN CENTER	1	Admin Office 1 (remote from office)	150	280	130	
	1	Admin Office 2 (remote from office)	150	280	130	
	1	Admin Office 3 (remote from office)	0	554	554	Not in program
DINING & MULTI-PURPOSE	1	Student Dining Room	4,650	4,560	-90	
	1	Hybrid Kitchen (includes freezer/cooler)	1,000	1,432	432	
	1	Servery (2 serving lines)	890	1,239	349	Updated program req. = 3 lines
	1	Kitchen Office	100	100	0	
	1	Unisex Kitchen Toilet	75	75	0	
	1	Unisex Kitchen Toilet	75	75	0	
	1	Kitchen Staff Lockers	300	0	-300	In Kitchen, 12 lockers
	1	Recycling	100	0	-100	In Dining
	1	Kitchen Storage	200	198	-2	
	1	Dining Room Storage (Table)	500	524	24	
SP EC	1	Library	2,280	2,981	701	
BUILDING SUPPORT	1	4HR Vestibule / Annex Link	780	483	-297	
	1	All Other Vestibules	0	401	401	2 additional, not in program
	1	Elevator 1st Floor	200	90	-110	
	1	Elevator 2nd Floor	100	90	-10	
	1	Elevator 3rd Floor	100	90	-10	
	1	Elevator Machine Room	0	64	64	Not in program
	1	1st Floor Lobby	0	1,251	1,251	Not in program
	1	1st Floor Corridor w/Lockers	2,250	1,405	-845	
	1	2nd Floor Corridor w/Lockers	2,250	3,672	1,422	
	1	3rd Floor Corridor w/Lockers	1,125	3,672	2,547	
	1	Toilet Room 1 (Boys, Girls, Staff/Unisex & Jan.)	760	860	100	
	1	Toilet Room 2 (Boys, Girls, Staff/Unisex)	690	860	170	
	1	Toilet Room 3 (Boys, Girls, Staff/Unisex)	690	860	170	
	1	Toilet Room 4 (Boys, Girls, Staff/Unisex)	0	546	546	Not in program
	1	Toilet Room 5 (Boys, Girls, Staff/Unisex)	0	546	546	Not in program
	1	Janitor	0	64	64	Not in program
	1	Janitor	0	64	64	Not in program
	1	Janitor	0	64	64	Not in program
	1	Stair 1 @1st	400	385	-15	
	1	Stair 1 @2nd	400	396	-4	
	1	Stair 1 @3rd	400	396	-4	
	1	Stair 2 @1st	400	330	-70	
	1	Stair 2 @2nd	400	330	-70	
	1	Stair 2 @3rd	400	330	-70	

1 Stair 3 @1st	400	330	-70	
1 Stair 3 @2nd	400	330	-70	
1 Stair 3 @3rd	400	330	-70	
1 Mechanical Room	1,100	760	-340	
1 IDF	280	294	14	
1 IDF	0	236	236	Not in program
1 Electrical Room	200	190	-10	
1 Electrical Room	0	190	190	Not in program
1 Water Room (Sprinkler Pump)	0	235	235	Not in program
1 Storage	0	186	559	Not in program
Program Total	50,275	92%	60,543	93% 10,641
Envelope, Partition & Shafts	4,022	8%	4,843	7%
Total:	54,297		65,386	
Planned Annex GSF Area 1st flr.:			16,042	
Planned Annex GSF Area 2nd flr.:			16,107	
Total GSF Program vs Concept Plan:			32,149	-22,148